



8/17/66

BENDIX SYSTEMS DIVISION ANN ARBOR, MICH.

NO.

REV.NO.

Grenade Transmitter Operational  
Verification Tests

ATM 472

PAGE 1 OF 1 PAGES

This is an unscheduled ATM covering the Grenade Transmitter Operational Verification Tests.

Using the proposed Grenade Launch Assembly (G. L. A.) Test Set, it will be possible to furnish power to the grenade transmitters when they are installed in the G. L. A. package and check for functional operation.

The required test points will be provided in the G. L. A. package for delivering power to the transmitter which will turn on the transmitter immediately. A 30 MHz receiver probe will be inserted into the grenade tube and the 30 MHz transmitter output will be verified.

Prepared by: J. Tupman  
J. Tupman

Approved by: R. W. Shay  
R. W. Shay